

NIPPON KAIJI KYOKAI

Approval No. NKY-3312 Certificate No. TA16709E



TYPE APPROVAL FOR WELDING CONSUMABLE

Brand:

MG-T1CM

Applicant:

Kobe Steel, Ltd., Fukuchiyama Plant

Fukuchiyama, Kyoto, Japan

Manufacturer:

Kobe Steel, Ltd., Fukuchiyama Plant

Fukuchiyama, Kyoto, Japan

Grade:

Manufacturer's Specification

Welding Process:

Semi-Automatic Welding (MAG Welding)

Welding Positions and Diameter of Wire:

See Table 1 on the reverse side

Current:

DCEP

Shielding Gas:

Ar+CO₂

Mixing ratio of shielding gas: "M2" specified in Table M6.14,

Chapter 6, Part M of the NK Rules

Chemical Composition:

See Table 2 on the reverse side

Mechanical Properties:

See Table 3 on the reverse side

Applicable Parent Material:

 $1.00 \sim 1.25\%$ Cr-0.5%Mo steels intended for Boilers

Specific Grade:

Class 1 and Class 2 of Grade 11 specified in ASTM A387

and Equivalent Steels

Remarks:

For annual inspection, test requirements and mechanical properties are to

comply with Table 3 and Table 4 (see the reverse side).

THIS IS TO CERTIFY that the above mentioned welding consumable has been approved by the NIPPON KAIJI KYOKAI in accordance with the requirements of the Society's Rules.

This Certificate will remain in force until 15 February 2017. Issued at Tokyo on 16 February 2016.

T. Imamura
General Manager

Material and Equipment Department

Note: The validity of this certificate may be renewed by endorsement on the attached sheet upon completion of the annual inspections.



Table 1 Welding Positions and Diameter of Wire

Butt W		Fillet Weld		
Flat:	1.2mm	Flat:	1.2mm	
		Horizontal Vertical:	1.2mm	
Horizontal:	1.2mm	Horizontal:	1.2mm	
Overhead:	1.2mm	Horizontal Overhead:	1.2mm	
		Overhead:	1.2mm	
Vertical Upward:	1.2mm	Vertical Upward:	1.2mm	
Vertical Downward:	Not Applicable	Vertical Downward:	Not Applicable	

Table 2 Chemical Composition of Wire

		10010 2	. 0110111					
С	Si	Mn	P	S	Cu	Ni	\mathbf{Cr}	Mo
	0.30	0.60	0.005	0.005	0.05	0.00	1.10	0.40
0.12	~	~	0.025	0.025	0.35	0.20	~	~
max.	0.90	1.40	max.	max.	max.	max.	1.60	0.65

Table 3 Requirements of Mechanical Properties after Stress Relief Annealing (1hour at $690^{\circ}\text{C} \pm 15^{\circ}\text{C}$)

Deposited Metal Tensile Test			Butt Weld Tensile Test	
Tensile strength	Yield point	Elongation	Tensile strength	
(N/mm ²)	(N/mm^2)	(%)	(N/mm ²)	
560 min.	460 min.	19 min.	515 min.	

Table 4 Test Requirements for Annual Inspection

Table 4 Test Requirements for Timitar Inspection				
T7: 1 0	Test assembly ^{1), 2), 3),4)}			Kind and number of test specimens to be taken from test assembly
Kind of test	Number	Plate thickness (mm)	Welding position	Tensile test specimen ^{5),6)} : 1
Deposited metal test	1	20	Flat	

Notes:

- 1) The approved specific grades of applicable parent material are to be applied. Other parent material with appropriate buttering may be applied subject to the approval of the Society.
- 2) Shape and dimension of test assembly are to be in accordance with Fig. M6.1, Chapter 6, Part M of the NK Rules.
- 3) Test assembly is to be welded in accordance with 6.4.5, Chapter 6, Part M of the NK Rules.
- 4) Stress relief annealing is to be conducted under the condition of 1hour at 690° C \pm 15° C.
- 5) Kind of test specimen is to be U1A specified in Table M3.1, Chapter 3, Part M of the NK Rules.
- 6) Mechanical properties are to comply with the requirements specified in Table 3.

The validity of the	his certificate has been renewed	The validity of this certificate has been renewed		
until	1 5, FEB. 2018	until 1 5. FEB. 2023 •		
	Date: 3 1. AUG 2017 Surveyor	Date: 28. MAR MAN		
The validity of the	nis certificate has been renewed	The validity of this certificate has been renewed		
until	1 5. FEB. 2019	until 15. FEB. 2024 .		
	Date: 30, NAT. 010 Kakimoto Surveyor	Date: 28. MAR 2021		
The validity of th	nis certificate has been renewed	The validity of this certificate has been renewed		
until	1 5. FE B. 2020	until		
	Date: 29, MAR. 2019	Date:		
	Surveyor	Surveyor		
The validity of th	nis certificate has been renewed	The validity of this certificate has been renewed		
until	1 5. FEB. 2021 .	until		
	Date: 27. MAR 2020	Date:		
	Surveyor	Surveyor		
The validity of th	nis certificate has been renewed	The validity of this certificate has been renewed		
until	1 5. FEB. 2022	until		
	Date: 30. WAR. 2021	Date:		
_	Surveyor	Surveyor		